ELECTRICAL DESIGN GROUP
ELECTRICAL BUILDING SERVICES CONSULTANTS
P.O. Box 15, SHERWOOD Q. 4075
Phone: 0418 893 338
Web Site: www.edg.net.au Email: brisbane@edg.net.au

C3584a - METROPOLE HOTEL, PROSERPINE **C3584a-0008(A).xls**

DISTRIBUTION BOARD DB-D

REVISION A - 09 NOVEMBER 2026

		REV
FAULT CURRENT:	6kA	A
CHASSIS SIZE:	36 POLES	A
CHASSIS RATING:	250A	A
PHASES:	A	A
DB-D IS INTEGRAL TO THE MSB. PROVIDE THE DB WITH A FULL WIDTH EMPTY DIN RAIL TO ACCOMMODATE FUTURE CONTACTORS AND CONTROLS IN ADDITION TO THE CONTROLS PROVIDED AS PART OF THE INITIAL WORKS. . PROVIDE THE DB WITH SURGE PROTECTION.		A

CIRC	PH	CIRCUIT BREAKER (amps)	CONTROL EQUIPMENT	CABLE SIZE (mm^2)	LOCATION	CIRCUIT USE	
P1	1	20	RCBO	2.5	BEER GARDEN	TV	A
P2	1	20	RCBO	2.5	BEER GARDEN	LED SCREEN	A
P3	1	20	RCBO	2.5	BEER GARDEN	LED SCREEN	A
P4	1	20	RCBO	2.5	BEER GARDEN	STAGE	A
P5	1	20	RCBO	2.5	BEER GARDEN	GPOs	A
P6	1	20	RCBO	2.5	BEER GARDEN	STAGE	A
P7	1	20	RCBO	2.5	BEER GARDEN	SEATING	A
P8	3	63	MCB	16.0	70 MAIN ST	DB-7	A
P9	3	63	MCB	16.0	DRIVE THROUGH	DB-5	A
L1	1	20	RCBO PE ON DUSK TC OFF 3.00AM	2.5		ENTRY LIGHTS	A
L2	1	20	RCBO PE ON DUSK TC OFF 3.00AM	2.5		SIGN	A
L3	1	20	RCBO PE ON DUSK TC OFF 3.00AM	2.5	BEER GARDEN	FESTOONS	A
L4	1	20	RCBO PE ON DUSK TC OFF 3.00AM	2.5	BEER GARDEN	FESTOONS	A
L5	1	20	RCBO PE ON DUSK TC OFF 3.00AM	2.5	BEER GARDEN	LIGHTS	A
L6	1	20	RCBO PE ON DUSK TC OFF 3.00AM	2.5	BEER GARDEN	SIGN	A

ELECTRICAL DESIGN GROUP BRISBANE PTY LTD ACN 092 710 793
TRADING AS – ELECTRICAL DESIGN GROUP ABN 96 092 710 793