ELECTRICAL DESIGN GROUP
ELECTRICAL BUILDING SERVICES CONSULTANTS
P.O. Box 15, SHERWOOD Q. 4075
Phone: 0418 893 338
Web Site: www.edg.net.au Email: brisbane@edg.net.au

C3763a - REDLANDS SPORTING CLUB - STAGE 2 **C3763a-0006(B).xls**

DISTRIBUTION BOARD DB-C

REVISION B - 04 NOVEMBER 2026

	REV
MODIFY THE EXISTING DISTRIBUTION BOARD DB-D AS NECESSARY TO ACCOMMODATE THE FOLLOWING CIRCUITS. REMOVE ALL EXISTING SWITCHGEAR MADE REDUNDANT BY THE WORKS AND UPDATE THE SCHEDULE AT PRACTICAL COMPLETION. REMOVE THE FOUR THREE PHASE RCD UNITS IN THE LOAD CENTRE ADJACENT DB-C AND REPLACE THE ASSOCIATED FOUR THREE PHASE MCBS IN DB-C WITH THREE POLE THREE PHASE RCBOS. RECONNECT THE FOUR EXISTING THREE PHASE CIRCUITS.	A

CIRC	PH	CIRCUIT BREAKER (amps)	CONTROL EQUIPMENT	CABLE SIZE (mm^2)	LOCATION	CIRCUIT USE	
P1	1	20	RCBO	2.5	DARTS	DARTS	A
P2	1	20	RCBO	2.5	DARTS	DARTS	A
P3	1	20	RCBO	2.5	CIRCULATON	CLEANING	A
P4	1	20	RCBO	2.5	DARTS	LED SCREEN	A
CB7	1	20	RCBO	2.5		LIGHTING	A
CB9	1	20	RCBO	2.5		LIGHTING	A
CB25	1	20	RCBO	2.5		LIGHTING	B

ELECTRICAL DESIGN GROUP BRISBANE PTY LTD ACN 092 710 793
TRADING AS – ELECTRICAL DESIGN GROUP ABN 96 092 710 793